BANGALORE DIVISION.

ADVERTISEMENT.

The 17th October 1891.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 31st October 1891, for restoring the Ujini Gaurammanakere Tank. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 31st October 1892.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring the Ujini Gaurammanakere Tank," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Improving Ujini Tank, Registered No.—Dodballapur Taluk.

Items of Work.	Per.	Quantity.
Bund.		
Earthwork for breach	C. Yd.	38,890
Earthwork	Do	84,342
Removing silt	Do	4,930
New stone work	Do	5,346
Old stone work	Do	1,045
B. M. stones	No.	2
Grade stones with index stones, &c.	Do	30
Right Sluice.		
Constructing new sluice	Lump Sum.	
Waste Weir.		
Earthwork	C. Yd.	2,330
Burnt brick in chunam	C. Ft.	1,889
Chunam plastering	Sq.	12·87
Stone slabs	S. Ft.	382
New stone sujikat	C. Yd.	393
Benching rock	Item.	1
New stone work	C. Yd.	11
Excavating the distribution channel	Lump Sum.	

R. T. SCALDWELL,
Executive Engineer.